

Door Schedule				
Mark	Width	Height		
GROUND FLOOR LEVEL				
D1	2' - 6"	7' - 0"		
D2	3' - 0"	7' - 0"		
MD	4' - 0"	7' - 0"		

NO IE	<u>=</u> :
•	THE FLOOR HEIGHT IS 1

Window Schedule				
Mark	Width	Height	Area	
GROUND FLOOR LEVEL				
KW	4' - 0"	3' - 0"	12 ft²	
V	2' - 0"	1' - 6"	15 ft²	
W1	5' - 0"	4' - 0"	100 ft <sup>2</sup>	

	vvindow	Schedule			SHELVES & LO	JF 15
Mark	Width	Height	Area		Name	Are
ROUND F	LOOR LEVE	_		-	GROUND FLOOR LE	VEL
V	4' - 0"	3' - 0"	12 ft²		C.SHELVE	13 ft²
	2' - 0"	1' - 6"	15 ft²		C.SHELVE	9 ft²
1	5' - 0"	4' - 0"	100 ft <sup>2</sup>		LOFT	60 ft <sup>2</sup>
				-	LOFT	73 ft <sup>2</sup>

Opening schedule may change according to the structural design.

NOTES:

- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.
- The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

REV.

ITERATION - R3

## AREA STATEMENT

Area Schedule

Name	Area
ROAD LEVEL	
SITE	2354 ft <sup>2</sup>
	2354 ft <sup>2</sup>
PARKING LEVEL	
Area	245 ft <sup>2</sup>

245 ft<sup>2</sup> GROUND FLOOR LEVEL

Area	1152 ft²
	1152 ft²

**LEGENDS** 



**ARCHITECT** AR.V.ROHIT

## **Brick & Bolt**

Hive Space, Ground Floor, Ramalayam rd, Laxmi Cyber city, Kondapur, Hyderabad, Telangana 500084 Project

## **Mr.Venkat Reddy**

CRN	Drg. No.	Date
157915	A101	10/10/2022
Drawing Title		Scale
GROUND FLOOR PLAN		1:75

Area

155 ft<sup>2</sup>



