

Door Schedule				
Mark	Width	Height	Count	
GROUND FLOOR LEVEL				
D1	2' - 6"	7' - 0"	4	
D2	3' - 0"	7' - 0"	4	
MD	4' - 0"	7' - 0"	1	

Window Schedule						
Mark	Width	Height	Count	Area		
GROUND FLOOR LEVEL						
KW	4' - 0"	3' - 0"	1	12 ft²		
V	2' - 0"	1' - 6"	3	9 ft²		
W1	5' - 0"	4' - 0"	3	60 ft ²		

NOTE:

THE FLOOR HEIGHT IS 11'

Hive Space, Ground Floor, Ramalayam rd, Laxmi Cyber city,Kondapur, Hyderabad, Telangana 500084

Brick & Bolt

Project

Mr.Venkat Reddy

CRN Drg. No. Date
157915 A101 11/09/2022

Drawing Title Scale
GROUND FLOOR PLAN 1:75

NOTES:

- Opening schedule may change according to the structural design.
- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.
- The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

REV.

| ITERATION -| R4-STRUCTURE FRAMING

AREA STATEMENT

Area Schedule

Name	Area
ROAD LEVEL	·
SITE	2354 ft ²
	2354 ft ²
PARKING LEVEL	
Area	249 ft ²

249 ft² GROUND FLOOR LEVEL

	Area	1191 ft²
١		1191 ft²

LEGENDS



LOFTS

ARCHITECT

AR.V.ROHIT

