

Door Schedule					
Mark	Width	Height			
FIRST FLOOR LEVEL					
D1	2' - 6"	7' - 0"			
D2	3' - 0"	7' - 0"			
D3	3' - 6"	7' - 0"			

V	Window Schedule				
Mark	Width	Height			
FIRST FLOOR LEVEL					
V	2' - 0"	2' - 0"			
W1	3' - 0"	4' - 0"			
KW	4' - 0"	3' - 0"			
W2	5' - 0"	4' - 0"			

## NOTES:

- Opening schedule may change according to the structural design.
- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.
- The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

REV.

CONCEPT - RO

## AREA STATEMENT

Area Schedule			
Name	Area		
FIRST FLOOR LEVE			
UTILITY-1	24 ft <sup>2</sup>		
UTILITY - 2	34 ft²		
CORRIDOR	109 ft <sup>2</sup>		
Area	1333 ft <sup>2</sup>		

**LEGENDS** 

ARCHITECT AR.V.ROHIT

## **Brick & Bolt**

Hive Space, Ground Floor, Ramalayam rd, Laxmi Cyber city,Kondapur, Hyderabad, Telangana 500084 Project

## Mr.Kumar

CRN	Drg. No.	Date
134652	A102	09/08/22
Drawing Title		Scale
TYPICAL FLOOR PLAN (1st &2nd)		1:70

