



LOFT AND SHELVES	
Name	Area
<b>FIRST FLOOR LEVEL</b>	
CEMENT SHELVE	27 ft <sup>2</sup>
CEMENT SHELVE	14 ft <sup>2</sup>
CEMENT SHELVE	19 ft <sup>2</sup>
CEMENT SHELVE	59 ft <sup>2</sup>
LOFT	10 ft <sup>2</sup>
LOFT	19 ft <sup>2</sup>
LOFT	28 ft <sup>2</sup>
LOFT	29 ft <sup>2</sup>
LOFT	60 ft <sup>2</sup>
LOFT	145 ft <sup>2</sup>

PLEASE NOTE - The above areas will be doubled in the quotation as it is applicable for the Typical 2nd floor aswell.

**NOTES:**

- Opening schedule may change according to the structural design.
- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.

The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

REV.  
ITERATION -R1

**AREA STATEMENT**

Area Schedule	
Name	Area
<b>FIRST FLOOR LEVEL</b>	
UTILITY-1	17 ft <sup>2</sup>
CORRIDOR	23 ft <sup>2</sup>
UTILITY - 2	34 ft <sup>2</sup>
Area	1425 ft <sup>2</sup>

**LEGENDS**

ARCHITECT  
AR.V.ROHIT

Door Schedule		
Mark	Width	Height
<b>FIRST FLOOR LEVEL</b>		
D1	2' - 6"	7' - 0"
D2	3' - 0"	7' - 0"
MD	3' - 6"	7' - 0"

Window Schedule		
Mark	Width	Height
<b>FIRST FLOOR LEVEL</b>		
KW	4' - 0"	3' - 0"
V	2' - 0"	2' - 0"
W1	3' - 0"	4' - 0"
W2	5' - 0"	4' - 0"

**Brick & Bolt**  
Hive Space, Ground Floor,  
Ramalayam rd,  
Laxmi Cyber city,Kondapur,  
Hyderabad, Telangana 500084

Project  
**Mr.Kranthi Kumar**

CRN  
134652

Drg. No.  
A102

Date  
09/10/2022

Drawing Title  
TYPICAL FLOOR PLAN (1st &2nd)

Scale  
1 : 70

