



Door Schedule			
Mark	Width	Height	Count
<b>FIRST FLOOR LEVEL</b>			
D1	2' - 6"	7' - 0"	4
D2	3' - 0"	7' - 0"	2
MD2	3' - 6"	7' - 0"	1
MD	4' - 0"	7' - 0"	1
<b>FIRST FLOOR LEVEL</b>			<b>8</b>

Window Schedule				
Mark	Width	Height	Count	Area
<b>FIRST FLOOR LEVEL</b>				
V	2' - 0"	2' - 0"	3	12 ft <sup>2</sup>
KW	3' - 0"	3' - 0"	1	9 ft <sup>2</sup>
W1	3' - 0"	4' - 0"	1	12 ft <sup>2</sup>
W3	5' - 0"	4' - 0"	3	60 ft <sup>2</sup>
			<b>8</b>	<b>93 ft<sup>2</sup></b>

**NOTES:**

- Opening schedule may change according to the structural design.
- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.

The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

**REV.**  
ITERATION-R1

**AREA STATEMENT**

Area Schedule	
Name	Area
<b>FIRST FLOOR LEVEL</b>	
UTILITY	29 ft <sup>2</sup>
CORRIDOR	142 ft <sup>2</sup>
<b>Area</b>	<b>636 ft<sup>2</sup></b>

**LEGENDS**

**ARCHITECT**  
AR.V.ROHIT

**Brick & Bolt**  
Hive Space, Ground Floor,  
Ramalayam rd,  
Laxmi Cyber city,Kondapur,  
Hyderabad, Telangana 500084

Project  
**Mr.Vijay Kumar**

CRN  
157239

Drawing Title  
FIRST FLOOR PLAN

Drg. No.  
A102

Date  
09/29/22

Scale  
1 : 50

**NORTH**