

Door Schedule				
Mark	Width	Height		
THIRD FLOOR LEVEL				
D1	2' - 6"	7' - 0"		
D2	3' - 0"	7' - 0"		
D4	4' - 0"	7' - 0"		

Window Schedule					
Mark	Width	Height			
THIRD FLOOR LEVEL					
V	2' - 0"	2' - 0"			
W1	3' - 0"	4' - 0"			
KW	4' - 0"	3' - 0"			
W2	5' - 0"	4' - 0"			

## NOTES:

- Opening schedule may change according to the structural design.
- The layout of columns and beams may change according to the structural design.
- Number of steps may change according to the plinth and parking height desired.
- Thickness of walls is only proposed. It may have to change based on the structural design to avoid column/beam projections.
- The Contractor and the Consultant shall bear no responsibility whatsoever where any drawings provided by it/them in relation to the project / Said Works, does not comply with any applicable laws including the bye-laws of the building/society where such project is situated. Further, it is clarified that it shall be the responsibility of the Owner to ensure any and all compliance of the drawings provided by the Contractor/Consultant.

REV.

CONCEPT - RO

## AREA STATEMENT

Area Schedule		
Name	Area	
THIRD FLOOR LEVEL		
UTILITY	34 ft <sup>2</sup>	
BALCONY	56 ft <sup>2</sup>	
CORRIDOR	109 ft <sup>2</sup>	
Area	1301 ft <sup>2</sup>	

**LEGENDS** 

ARCHITECT AR.V.ROHIT

## **Brick & Bolt**

Hive Space, Ground Floor, Ramalayam rd, Laxmi Cyber city,Kondapur, Hyderabad, Telangana 500084 Project

## Mr.Kumar

CRN	Drg. No.	Date
134652	A103	09/08/22
Drawing Title		Scale
THIRD FLOOR PLAN	1:70	

